



**PROJECT** Bonnarigo Buildings

**BUILDING OWNER** Russ Bonnarigo Sr.  
P.O. Box 97  
Blairsville, PA

**AREA** One Hundred Ninety Eight Thousand Square Feet

**DESCRIPTION** Two separate exposed fastener metal roof systems had been experiencing roof leaks for many years. Many past attempts were made by the building owner to repair roof leaks with asphalt-based products but with minimal success.

The translucent skylight panels were first flagged off to provide a safe working environment for our crew to apply the rubber coating system. After the rust inhibitor was installed and the pressure washing was completed, all seams and fasteners were sealed. Each fiberglass skylight panel was then coated with #7145 clear rubber coating. Two applications of #7140 rubberized coating were applied at a total coverage rate of 3 gallons per 100 square feet before the 10-year leakage warranty was issued.

**ARCHITECT/SPECIFIER** Tuscano-Maher Roofing, Inc.

